

TF System® Labor Estimating Guidelines

The following guidelines are based upon actual construction projects and working conditions. Please keep in mind that these figures are contingent upon good quality footings to build on and motivated, competent crews to erect the forms. Weather or job site conditions may affect your actual time performance. These timelines reflect the average amount of time to erect TF wall forms on pre-built footings. Pouring time has not been included.

<u>4' High Wall Forms:</u>	Experienced Crew (4 men)	Non-experienced Crew (4 men)
Basic walls	450 l/ft/day	325 l/ft/day
Walls w/pre-made pilasters	265 l/ft/day	200 l/ft/day
Walls w/ pilasters/brick ledge	205 l/ft/day	162 l/ft/day

8-10' High Wall Forms 1st Story:

Basic walls (few openings)	180 l/ft/day	112 l/ft/day
Moderate-Heavy openings/corners	110 l/ft/day	72 l/ft/day

8-10' High Wall Forms 2nd Story:

Basic Walls (few openings)	135 l/ft/day	86 l/ft/day
Moderate-Heavy openings/corners	92 l/ft/day	55 l/ft/day



Labor Estimating

TF System ©
185 East Walnut Street
Sturgeon Bay, WI 54235 USA
800-360-4634

Revision Date: 5/25/05

Page Number: